MEC
MEDICAL LIMITED

Medical Gas Test & Commissioning Kit

SPECIFICATION SHEET

- A complete set all in one box to carry out Test & Commissioning
- Includes Pressure & Flow, AGSS Test & Commissioning, Male Anti Confusion NIST, Anti Confusion Probes and Standard Purging test kits
- In compliance with HTM02-01 and relevant European Standards and all preceding standards.

MEC Medical Ltd test equipment allows you to regularly check that medical gas pipelines are operating correctly to HTM02-01 guidelines.

A comprehensive set is available to test and calibrate medical gas pressure, flow and vacuum, ensure terminal units and NISTS are gas specific and that active Anaesthetic Gas Scavenging systems are adjusted to provide optimal performance. Particulate matter testing with purging allowing the check for particulate contamination within the pipeline as well as purging from terminal outlet.

CE

Supplied by

MEC
MEDICAL LIMITED

MEC Medical Limited, Unit 3, Trust Industrial Estate,
Wilbury Way, Hitchin, Hertfordshire. SG4 0UZ. United Kingdom
T: +44 (0) 1462 436396 F: +44 (0) 1462 432411
sales@mecmedical.com www.mecmedical.com